



& ASSOCIATES, INCORPORATED
PROFESSIONAL ENGINEERS & LAND SURVEYORS

102 Asma Boulevard
Suite 305
Lafayette, LA 70508

(337) 232-5182
FAX (337) 237-7132

www.dsaengineering.com

March 20, 2018

TO ALL HOLDERS OF PLANS
AND SPECIFICATIONS:

RE: Nona Street Drainage Improvements
City of Breaux Bridge, Louisiana
Addendum #1
(DSA # 4638.12)

ATTENTION:

Attached is ADDENDUM NO. 1 for the subject project. Please include it in your set of specifications and consider it when making your bid.

Sincerely,

DOMINGUE, SZABO & ASSOCIATES, INC.

Beau Desormeaux, PE

RBD/
Enclosure(s)

UNOFFICIAL COPY

ACEC

American Council of
Engineering Companies

**ADDENDUM TO
CONTRACT DOCUMENTS
AND SPECIFICATIONS**

**NONA STREET DRAINAGE IMPROVEMENTS
FOR THE CITY OF BREAUX BRIDGE, LOUISIANA
(DSA No. 4638.12)**

ADDENDUM NO. 1

March 20, 2018

The following items shall take precedence over referenced to counterparts in the specifications, contract drawings and any other documents in conflict herewith.

- Item No. 1** As a **General Note**– The contract time for the project is 120 calendar days.
- Item No. 2** Refer to the Specifications and Contract Documents, Section 02720 – Storm Sewerage System, Part 3 - EXECUTION, As a **As a note of EMPHASIS:** A2000 PVC piping shall be installed on minimum 4” thick compacted 610 gradation limestone bed. Limestone bedding material shall extend to the spring line of the pipe. Any over excavation shall be backfilled with compacted limestone.
- Item No. 3** Refer to the Specifications and Contract Documents, Section 02720 – Storm Sewerage System, Part 3 - EXECUTION, As a **As a note of EMPHASIS:** Flushing Storm Drainage Lines: If storm sewer lines are found to contain sand, gravel, or other foreign matter when inspected by the Engineer, they shall be flushed with a sufficient volume of water to remove all foreign matter prior to final acceptance. The Contractor shall furnish the water at no additional cost (no direct pay, include cost in unit price bid items for pipe) to the Owner.
- Item No. 4** Refer to the Specifications and Contract Documents, Section 02720 – Storm Sewerage System, Part 3 - EXECUTION, As a **As a note of EMPHASIS:** All disturbed ground both in the right-of-way and in the drainage servitude located in front and along the side property line at 470 Nona shall be sodded with St. Augustine sodding, paid under the unit price item “Slab Sodding”, per square yard. All other disturbed areas shall be hydro-seeded in accordance with the specification and paid under the unit price item “Hydro-Seeding”, per acre.

Received by: _____

Signed: _____

Dated: _____

Company: _____

**FAX THIS SIGNED PAGE TO DOMINGUE, SZABO & ASSOCIATES, INC. AT
337-237-7132; OR RESPOND TO EMAIL ACKNOWLEDGING RECEIPT OF ADDENDUM**

End of Addendum No. 1

