



& ASSOCIATES, INCORPORATED

102 Asma Blvd, Suite 305
Lafayette LA 70508

(337)232-5182
FAX (337)237-7132

www.dsaengineering.com

March 21, 2023

TO ALL HOLDERS OF PLANS
AND SPECIFICATIONS

Re: Wastewater Treatment Plant Improvements
For the City of Breaux Bridge, LA
Addendum #2
(DS&A #4807.02)

ATTENTION:

Attached is ADDENDUM #2 for the subject project. Please include it in your set of project documents and consider it when preparing your bid.

Sincerely,

DOMINGUE, SZABO & ASSOCIATES, INC.

Ronald (Beau) Desormeaux III, P.E.

American Council of
Engineering Companies

**ADDENDUM TO
CONTRACT DOCUMENTS
AND SPECIFICATIONS**

**WASTEWATER TREATMENT PLANT UPGRADE
FOR THE
CITY OF BREAUX BRIDGE, LA**

ADDENDUM NO. 2

March 21, 2023

The following items shall take precedence over referenced to counterparts in the specifications, contract drawings and any other documents in conflict herewith.

Item No. 1 Refer to the Contract Drawings, Sheet 3: **AS A POINT OF CLARIFICATION:** Contractor will not be required to remove and dispose of all vegetation located in cell 1, only that which impedes the Contractor from installing floating aerators. The note was included in the plan to notify the Bidder of the presence of floating vegetation in cell 1.

Item No. 2 Refer to the Contract Drawings, Sheets 11 & 12: Access block-outs at lower level of headworks will be allowed for form removal if necessary for constructability of the structure. If Contractor requires the need for form removal via access openings, block-outs shall be properly covered and secured with aluminum access hatches. Contractor will **NOT** be allowed to fill lower level with sand, fillcrete, or any other material to serve as forms for the elevated slab.

Item No. 3 Refer to the Contract Drawings, Sheets 5, 19, 20 & 21: **DELETE** the requirement to remove and replace sluice gates 1, 4, & 5. Only sluice gates 2 & 3 will be removed and replaced in this project. All other work depicted on the above sheets, including walkways, grating, guardrail at all discharge point locations, etc., will be required.

Item No. 9 **PRIOR APPROVAL LIST:** The following manufacturers' equipment may be considered for use on this project (they have received prior approval subject to the following):

The Engineer may allow minor deviations (e.g. sloped floor on vortex grit removal units) subject to the Engineer's judgment as to whether such deviations would detract from the quality, reliability or function of the equipment. The equipment manufacturer shall be responsible for any and all redesign required to accommodate their equipment. All drawings and calculations detailing the deviations from the plans and specifications shall be submitted to the Engineer with the shop drawings for approval. Drawings must be in AutoCad 2000 or more recent format and must be stamped by an Engineer licensed in the State of Louisiana. Submit both hard copies and electronic copies for approval.

Prior approval of other manufacturers' equipment shall in no way relieve the Contractor of responsibility for submitting the specified shop drawings for approval or complying fully with all provisions of the specifications and drawings.

If prior approved equipment is used, the contractor shall, at his own expense, make any changes or additions in the structures, piping, electrical, etc. as necessary to accommodate the equipment. If engineering is required due to substitution of prior approved equipment, the contractor shall furnish and pay for all such engineering services. No qualifications or exceptions listed in prior approval submittals shall in any way alter or serve as substitute provisions relative to this contract.

<u>Section</u>	<u>Description of Items</u>	<u>Approved Mfr.</u>
00300	Concrete Water-proofing Admixture	Master Builders Solutions
11330	Chain & Rake Bar Screen System	Aqualitic
11336	Screenings, Washings, and Compacting System	Aqualitic
11350	Fabricated Gates	Waterman
11350	Fabricated Gates	RW Gate
11362	Skimmers	Envirodyne
11370	Floating Aerators	Aerator Solutions