



& ASSOCIATES, INCORPORATED
PROFESSIONAL ENGINEERS & LAND SURVEYORS

102 Asma Boulevard
Suite 305
Lafayette, LA 70508

(337)232-5182

www.dsaengineering.com

June 2, 2023

TO ALL HOLDERS OF PLANS
AND SPECIFICATIONS:

RE: Headworks Rehabilitation Ambassador Caffery Wastewater
Treatment Plant
Lafayette Consolidated Government
Lafayette Utilities System
Addendum No. 1
(DSA No. 4908.11)

ATTENTION:

Attached is ADDENDUM NO. 1 for the subject project. Please include it in
your set of specifications and consider it when making your bid.

Sincerely,

DOMINGUE, SZABO & ASSOCIATES, INC.

Chris Richard, PE

CKR/
Enclosure(s)

**ADDENDUM TO
CONTRACT DOCUMENTS
AND SPECIFICATIONS**

**HEADWORKS REHABILITATION AMBASSADOR CAFFERY
WASTEWATER TREATMENT PLANT
(DSA No. 4908.11)**

ADDENDUM NO. 1

JUNE 2, 2023

The following items shall take precedence over referenced to counterparts in the specifications, contract drawings and any other documents in conflict herewith.

Item No. 1 Refer to the Specifications and Contract Documents, Section 09950 – Rehabilitating Headworks; page 4 – Warranty **CHANGE** to the following:

“All materials and workmanship shall be guaranteed for **ten (10) years** from date of final acceptance of the project. The Contractor shall be responsible to make required corrections or adjustments at no cost to the Owner during the guarantee period.”

Item No. 2 Refer to the Specifications and Contract Documents, Section 09950 – Rehabilitating Headworks. As a note of clarification, the minimum coating thickness shall be 500 mils. Note that this thickness is in addition to any material used in the surface repair of the walls. Thickness is measured from finished concrete walls.

Item No. 3 Refer to the Specifications and Contract Documents, drawings. Upon completion of rehabilitation work, the baffle shall be removed and salvaged to the Owner. Anchor bolts shall remain for future use.

Item No. 4 Refer to the Specifications and Contract Documents, drawings. Contractor to modify existing aluminum decking as required to accommodate new weir gate at no direct pay.

Item No. 5 **PRIOR APPROVAL LIST:** The following manufacturers’ equipment may be considered for use on this project (they have received prior approval subject to the following):

The Engineer may allow minor deviations subject to the Engineer’s judgment as to whether such deviations would detract from the quality, reliability or function of the equipment. The equipment manufacturer shall be responsible for any and all redesign required to accommodate their equipment. All drawings and calculations detailing the deviations from the plans and specifications shall be submitted to the Engineer with the shop drawings for approval. Drawings must be in AutoCad 2019 or more recent format and must be stamped by an Engineer licensed in the State of Louisiana. Submit both hard copies and electronic copies for approval.

Prior approval of other manufacturers’ equipment shall in no way relieve the Contractor of responsibility for submitting the specified shop drawings for approval or complying fully with ALL provisions of the specifications and drawings.

If prior approved equipment is used, the contractor shall, at his own expense, make any changes or additions in the structures, piping, electrical, etc. as necessary to accommodate the equipment. If engineering is required due to substitution of prior approved equipment, the contractor shall furnish and pay for all such engineering services. No qualifications or exceptions listed in prior approval submittals shall in any way alter or serve as substitute provisions relative to this contract.

<u>Section</u>	<u>Description of Items</u>	<u>Approved Mfr.</u>
09950	Concrete Rehabilitation System	Nukote Coating System
11345	SS Weir Gate	RW Gate Waterman Whipps

ACKNOWLEDGING RECEIPT OF ADDENDUM ON THE BID FORM

End of Addendum No. 1

